



NOTES:

1. ALL CONSTRUCTION SHALL BE IN CONFORMANCE WITH THE "STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION".
2. WHERE EXISTING CONCRETE IS TO BE REMOVED, IT SHALL FIRST BE SAWCUT AT THE NEAREST SCOREMARK.
3. BASE SHALL BE CRUSHED MISC. BASE PER "STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION".
4. TREE WELLS SHALL BE CONSTRUCTED PER STANDARD ST-II AT 40' INTERVALS.

NOTE:

NEW SIDEWALKS WILL REQUIRE CRUSHED MISCELANEOUS BASE.
 ○ SIDEWALKS (REPLACEMENT OF SIDEWALK) RECOMPACT EXISTING BASE MATERIAL.

CITY OF GARDENA

ENGINEERING DIVISION

TITLE:

COMMERCIAL SIDEWALK

APP. BY:

[Signature] 12/16/98
DATE

DESIGNED BY	A.W.D.	12/16/98
DRAWN BY		
CHECKED BY		

DWG. NO. **ST - 5B**